

# **St. Augustine Beach Flood Reduction - 7th, 8th, and 9th Street Drainage**

News Release Date  
12-21-2023

## **City of St. Augustine Beach Public Notice**

# **St. Augustine Beach Flood Reduction - 7th, 8th, and 9th Street Drainage**

\*\*\*UPDATED 05/08/2024\*\*\*

Construction work has begun on 7<sup>th</sup> Street. During this project, road access may be limited on the western section of 7<sup>th</sup> Street beginning near 208 7<sup>th</sup> Street. The contractor has ensured that residents will still be able to access their driveways during this work, however we ask that residents be patient when leaving and returning while workers and equipment are on-site.

## **SCOPE OF WORK**

The 7<sup>th</sup> 8<sup>th</sup> & 9<sup>th</sup> Street Drainage project consists of drainage improvements to 7th, 8th, and 9th Streets west of 2nd Avenue to alleviate recurrent flooding and reduce the potential for flood related losses. This project will also ensure adequate drainage conveyance to the City's master stormwater drainage system, located at the west end of the project site. This project will consist of the design, permitting, and construction of as-necessary drainage improvements that may include drainage structures, piping, swale construction, curb and gutter, and road improvements to reduce the frequency and severity of flooding within the project area.

A Town Hall meeting was held on November 2, 2023. See below files for meeting agenda and minutes/notes.

# CURRENT PROJECT PHASE: Construction

Construction is underway.

## PROJECT FUNDING:

This project is currently being funded by a State of Florida Legislative Appropriation Grant in the amount of \$90,000. However, due to the limited grant funding, the City will construct only the 7<sup>th</sup> Street portion of the improvements this fiscal year.

Budget funding for 8<sup>th</sup> and 9<sup>th</sup> Street Improvements have been requested in future fiscal year budget periods.

## 7TH STREET PROJECT SCHEDULE:

05/06: Staging of materials and equipment; Erosion & Sedimentation Control installation; begin removal of existing drainage pipe and structure. **COMPLETED** [✓](#)

05/09: Installation of new drainage pipe and structure. **COMPLETED** [✓](#)

05/14: Roadwork begins.

05/20: Curb installation.

05/27: Paving

06/01: Clean up.

06/17: Substantial completion.

*Please note that these dates are tentative and are subject to change.*

# ADDITIONAL INFORMATION:

## Contractor Information:

G & H Underground Construction Inc., 2315 Dobbs Rd, St. Augustine, FL 32086

For additional project information, contact the City’s Engineering Department:

Jason D. Sparks, P.E.	Derek Sands
Engineering Director	Engineering Inspector
(904) 471-2122	(904) 808-5901
<a href="mailto:jsparks@cityofsab.org">jsparks [at] cityofsab.org</a>	<a href="mailto:dsands@cityofsab.org">dsands [at] cityofsab.org</a>

If you have any questions regarding potential disruption to trash/recycling services during this project, please call the Public Works Department at 471-1119 or:

Russell Adams	Ken Gatchell
Assistant Public Works Director	Public Works Director
Cell 904-466-5757	Cell 904-669-4347
<a href="mailto:radams@cityofsab.org">radams [at] cityofsab.org</a>	<a href="mailto:kgatchell@cityofsab.org">kgatchell [at] cityofsab.org</a>

## HELPFUL LINKS:

- Have a concern or request regarding City operations? Click [here](#) to access the Resident Self Service page.**
- Have a question regarding stormwater management and City's National Pollutant Discharge Elimination System (NPDES) Program? Click [here](#).**

7th, 8th, & 9th Street Photos & Map 2 MB

Town Hall Presentation 31.47 MB

Town Hall Agenda 176.89 KB

Meeting Minutes and Notes 2.59 MB

[View in Google Maps](#)

**29.849295458273, -81.270095188867**