

Oceanside Circle Drainage & Pavement Improvements

City of St. Augustine Beach Public Notice

Oceanside Circle Drainage & Pavement Improvements

Updated: 04/20/2024

SCOPE OF WORK:

The City of St Augustine Beach has proposed drainage improvements and upgrading the substandard pavement on Oceanside Circle / Oceanside Drive east of A1A Beach Boulevard in an effort to mitigate isolated stormwater ponding primarily west of the curve. The proposed project will consist of adding approximately five (5) stormwater Inlets and 800 linear feet. of 15-inch diameter RCP and replacing 950 linear feet of chip and seal pavement with an asphaltic cement and an inverted crown.

Alternative suggestions have been discussed to acquire property and build pond at end of Circle or analyze for smaller pump station at end of Circle pumping to Linda Mar station.

CURRENT PROJECT PHASE:

Pre-Design

PROJECT FUNDING:

The City is currently working to secure legislative appropriations to fund this project.

ADDITIONAL INFORMATION:

For additional project information, contact the City's Engineering Department:

Jason D. Sparks, P.E.

Derek Sands

Engineering Director

Engineering Inspector

(904) 471-2122

(904) 808-5901

jsparks [at] cityofsab.org

[dsands \[at\] cityofsab.org](mailto:dsands@cityofsab.org)

HELPFUL LINKS:

Have a concern or request regarding City operations? Click [here](#) to access the Resident Self Service page.

Have a question regarding stormwater management and City's National Pollutant Discharge Elimination System (NPDES) Program? Click [here](#).

[View in Google Maps](#)

29.82540505928, -81.265244806183